

V. CAUTIONS:

V(a). CARE MUST BE TAKEN TO NOT OVER TORQUE FASTENERS.

V(b). DO NOT UNDER ANY CIRCUMSTANCE, STEP ON THE PANEL AT THE SEAMS, AND THE PANEL ENDS. THE ROOF PANEL MAY NOT SUPPORT THE WEIGHT OF A MAN AT THESE LOCATIONS WHICH COULD RESULT IN SERIOUS INJURY AND IT COULD AFFECT PANEL ALIGNMENT.

V(b1). CARE MUST BE TAKEN NOT TO STEP ON PANEL BETWEEN FIRST PURLIN AND EAVE WHEN FASTENING EAVE SCREWS. THIS MAY CAUSE PONDING OF WATER.

V(c). CARE MUST BE TAKEN IN PROTECTING PANELS FROM OTHER TRADES, DISSIMILAR METALS, AND POSSIBLE RUN OFF OF HVAC EQUIPMENT.

V(d). THE DETAILS CONTAINED IN THE FOLLOWING PAGES ARE MERELY RECOMMENDATIONS AS TO HOW "FLEXOSPAN, INC." MATERIALS SHOULD BE INSTALLED. THEY MAY REQUIRE ADAPTATIONS OR MODIFICATIONS FOR A SPECIFIC PROJECT AS CONDITIONS VARY IN BOTH BUILDING DESIGN AND LOCAL WEATHER PECULIARITIES.

V(e). INSURING WATER-TIGHTNESS ON ANY GIVEN PROJECT IS THE FUNCTION OF THE INSTALLER. THE ARCHITECT/GENERAL CONTRACTOR/INSTALLER MUST ACCEPT THE RESPONSIBILITY TO ADAPT THESE DETAILS TO MEET PARTICULAR BUILDING REQUIREMENTS AND FIELD CONDITIONS AND TO INSURE ADEQUATE WATER-TIGHTNESS.

V(f). THE INSTALLER CAN VIRTUALLY ASSURE WATER-TIGHTNESS IF THESE FLASHING DETAILS HAVE BEEN PROPERLY ADAPTED, ADEQUATE LAPS HAVE BEEN PROVIDED, CORRECT TYPE OF SEALANT USED, ALL JOINTS ADEQUATELY CAULKED, AND PROFESSIONAL WORKMANSHIP EMPLOYED.

V(g). "FLEXOSPAN" DOES NOT RECOMMEND "FSS-18" ROOF PANELS TO BE INSTALLED ON ROOFS WITH A PITCH LESS THAN 1/2" IN 12".



BOX 515 RAILROAD STREET
SANDY LAKE, PENNSYLVANIA 16145-0515
PHONE: 800-245-0396 • FAX: 724-376-3864

"FSS-18" STANDING SEAM DETAILS

DRAWN BY:

D. UREY

DATE:

12/3/25

CHECKED BY:

DATE:

GENERAL NOTES(CONT.)

DRAWING NO.

FSSI8-3